

Estimate for House for Maj
H. C. McDowell

Excavation	200 yds at 40 ct per-yd	\$ 80 00
Stone work	120 perch at 350 per-perch	42 000
Brick work		35 000
	Cistern Complete with Pump.	25 000
Windows	18 windows first-story at 40 ⁰⁰ / ₁₀₀	72 000
"	17 do Second " 30 ⁰⁰ / ₁₀₀	51 000
Doors	12 Doors first-story 45 ⁰⁰ / ₁₀₀	54 000
"	10 " Second " 18 ⁰⁰ / ₁₀₀	18 000
"	Sliding Doors to Library	9 500
"	Folding " " Chamber-	8 500
Arch	Wood work on Arch	10 500
Stairway	Stairway Complete	14 500
Base	Base Boards to first-story	32 500
"	" " " " Second "	17 500
Water-Clout	Water-Clout-Complete	54 000
Frame	Frame & Floors	97 500
Roof	Roofing Cornice &c	152 500
Mantles	two wooden mantles	200 000
"	Five Iron " "	15 000
Hearth	Seven Marble Hearths 10 ⁰⁰ / ₁₀₀	70 000
Grates	Seven Hackett-pt Grates & Tiles	51 500
Furnice	Furnice & Fixtures	49 500
Painting	Painting & Varnishing	37 500
Cornice	Cornice & Center-Pieces	21 000
		<u>8604 00</u>
	over-	